



REPUBLIC OF THE PHILIPPINES
Department of Health
NATIONAL CENTER FOR MENTAL HEALTH
Nueve de Febrero Street, Mandaluyong City, Philippines
BIDS AND AWARDS COMMITTEE



Telephone No. 531-9001 loc. 239

Telefax No. 5318318

E-mail: bacncmh@yahoo.com

Website: www.ncmh.gov.ph

Section VI
Specification
(INFRA – IB NO. 006 – 2024)

Public Bidding for Infrastructure Project No. 06-2024 - Construction of Covered Waiting Area at ERCI Complex CY 2024 – 45 Calendar Days

INSTRUCTION: Bidders must state here either “Comply” or “Not Comply” against each of the individual parameters of each Specification stating the corresponding performance parameter of the equipment offered. Statements of “Comply” or “Not Comply” must be supported by evidence in a Bidders Bid and cross-referenced to that evidence. Evidence shall be in the form of manufacturer’s un-amended sales literature, unconditional statements of specification and compliance issued by the manufacturer, samples, independent test data etc., as appropriate. A statement that is not supported by evidence or is subsequently found to be contradicted by the evidence presented will render the Bid under evaluation liable for rejection. A statement either in the Bidders statement of compliance or the supporting evidence that is found to be false either during Bid evaluation, post-qualification or the execution of the Contract may be regarded as fraudulent and render the Bidder or supplier liable for prosecution subject to the provisions of ITB Clause 3.1(a) (ii) and/or GCC Clause 2.1(a)(ii).

Technical Specifications Particulars	Requirements	Statement of Compliance
<p>1. Application of the Infrastructure Project No. 06-2024 - Construction of Covered Waiting Area at ERCI Complex CY 2024</p>	<p>SCOPE OF WORKS</p> <p>A. GENERAL REQUIREMENTS</p> <ol style="list-style-type: none"> 1. Mobilization. 2. Construction of Temporary Facilities (Barracks, Storage Area, Working/Fabrication Area, Temporary Septic Tank, Site Enclosure & Access and etc.) with Installation of Electrical and Water Temporary Sub - meter Fabrication and installation of Construction billboard. 3. Fabrication and Installation of the required 8 feet by 8 feet Commission of Audit (COA) Billboard w/ backing and stand, Complete with Necessary Accessories 4. Fabrication and Installation of the required 4 feet by 8 feet Project Billboard w/ backing and stand, Complete with Necessary Accessories 5. Installation of the Required Construction Safety Signages on all necessary areas with backing. 	

	<p>B. EARTHWORKS</p> <p>1. Excavation of Adobe Soil for the Structure's Foundation System, Application of Gravel Bedding and Termite Control Treatment, Soil Compaction and Backfilling</p>	
	<p>C. CONCRETE WORKS</p> <p>1. Fabrication and Installation of Reinforced Concrete Isolated Footings, Concrete Pedestals and Slab on Grade, 3000 psi.</p>	
	<p>D. STRUCTURAL STEEL AND ROOFING WORKS</p> <p>1. Fabrication of Roofing Framing System and Installation of Roofing Sheets, Fascia Flashing and other elements as per plan requirements and specifications</p>	
	<p>E. PAINTING WORKS</p> <p>1. Application of Quick Drying Enamel and Rust Inhibiting Primer on all Metal Surfaces</p>	
	<p>F. ELECTRICAL SYSTEM WORKS</p> <p>1. Supply and Installation of Lighting Fixtures and Orbit Fans, Complete with Accessories Necessary to meet the required functionality of the system.</p>	
	<p>G. PROVISIONAL ITEMS</p> <p>1. Processing of the Required Permits (DOH Permit to Construct, Building Permit and License to Operate) and Submission of As Built Plans upon Project Completion, Complete with all Necessary Documents.</p>	
	<p>H. CLEARING & GRUBBING/ DEMOBILIZATION</p> <p>1. Site Clearing and Grubbing, Includes Hauling of Debris and Construction Waste Prior Project Turn – Over.</p> <p>2. Demobilization.</p>	
CONFORME:		
<i>(Company Name)</i>		