

## REPUBLIC OF THE PHILIPPINES Department Of Health



## National Center for Mental Health

## LIST OF ITEMS FOR PUBLIC RE-BIDDING CY2023 SUPPLY, DELIVERY, INSTALLATION, COMMISSIONING, CONFIGURATION AND TESTING OF AUDIO AND VIDEO EQUIPMENT SYSTEMS

NO	ITEM CODE	ITEM DESCRIPTION	QTY	UNIT OF MEASU RE	UNIT PRICE	TOTAL PRICE
1	AVE2 3-01	AUDIO AND VIDEO EQUIPMENT	1	LOT	6,301,508.00	6,301,508.00
		Indoor LED Wall (Rear Access) with: - Screen Size: 6 meters x 3 meters - Resolution: 1536 x 768 - Pixel Pitch: <4 mm - Best Viewing Distance: ≥ 3.9 m - View Angle: H:140°; V:140° - Input Voltage: 200-240V AC - Video Processor: YES - Input Signal: HDMI, VGA, DVI - Output Signal: VGA, DVI - Production Switcher with 4 HDMI Input - Framing and steel structure, installation of equipment, configuration and commissioning Installation Site: Pag-Asa Hall	1	Set	1,878,966.00	1,878,966.00
		At least 98" Smart TV  NEO Quantum Processor 4K  Quantum HDR 32X  100% Color Volume with Quantum DOT  Ultra/Wide Viewing Angle with Anti-Reflection  Spacefit Sound with Dolby Digital Plus and Bluetooth Audio  Object Tracking Sound (OTS+)  Q-Symphony  Sound Output (RMS): 60W  Speaker Type: 4.2.2CH Installation Site: Administration Building Conference, PETRU Auditorium, BAC Conference Room, MCC Conference Room	4 Menta	Units	514,000.00	2,056,000.00

9 De Pebrero St., Brgy. Mauway, Mandaluyong City Tel. No.: 8531-9001 Fax: 8531-8682 Website: www.ncmh.gov.ph





Full HD (3LCD, 3-chip) projector technology systems  - 1.2x – 1.4x optical zoom  - At least 4, 000 lumens of color/white brightness plus full HD resolution (1920 x 1080)  HDMI, VGA, USB and wireless LAN connectivity with screen mirroring Installation Site: HRMO Conference Room, Quality Management Office, Office for Strategy Management	3	Units	55,100.00	165,300.00
15" Active Speakers - Rated Power: 1300W - Frequency Response: 55hz – 20kHz - Maximum SPL – 128 dB - Coverage Pattern – 900 x 600 - Audio I/Os: 2 XLR Combo, 1 XLR passthrough Installation Site: Pag-Asa Hall	6	Units	54,999.00	329,994.00
18" Active Subwoofers - Rated Power: 1500W - Frequency Response: 31hz – 150Hz - Maximum SPL – 131 dB - Audio I/Os: 2 XLR Combo, 2 XLR loop-outs Installation Site: Pag-Asa Hall	2	Units	94,599.00	189,198.00
10" Active Speakers (For Monitors) - Rated Power: 1300W - Frequency Response: 52hz – 20kHz - Maximum SPL – 125 dB - Audio I/Os: 2 XLR Combo, 1 XLR passthrough Installation Site: Pag-Asa Hall, HRMO Conference Room	4	Units	46,700.00	186,800.00
<ul> <li>(12 pieces) Surface-mount Loudspeaker</li> <li>2.25" Driver in a Ported Enclosure</li> <li>80W Peak Power Handling</li> <li>106 dB Max SPL</li> <li>130° H x 130° V Coverage Pattern</li> <li>70/100V with Multi-Tap Transformer</li> <li>Installation Site: Admin Conference</li> <li>Room, PETRU Auditorium</li> </ul>	6	Pairs	18,000.00	108,000.00
<ul> <li>12 Channel Analog Mixer</li> <li>Power Requirement: 100 – 240V</li> <li>Power Consumption: 22W</li> <li>Input Channels: 12 channels (Mono [MIC/LINE]: 4, Mono/Stereo [MIC/LINE]: 2, Stereo [LINE]: 2)</li> <li>Output Channels: Stereo Out: 2, Phones: 1, Monitor Out: 1, Aux Send: 2, Group Out: 2</li> </ul>	1	Unit	31,850.00	31,850.00

Installation Site: Pag-Asa Hall				
Mixer Amplifier - 5 Zone with USB/BT/FM - 5 Mic, 2 Aux - 70V/100V/4-16ohms Installation Site: Admin Conference Room, PETRU Auditorium	2	Units	36,855.00	73,710.00
8 Channel Mixer - Stereo Input - USB/Bluetooth Function Installation Site: HRMO Conference Room	2	Units	12,077.00	24,154.00
6 Channel Analog Mixer Installation site: PETRU Auditorium	1	Unit	17,550.00	17,550.00
Tripod Speaker Stand Installation Site: Pag-Asa Hall	4	Pieces	3,200.00	12,800.00
Pole Stand Installation Site: Pag-Asa Hall	2	Pieces	3,500.00	7,000.00
Speaker Cables Installation Site: Pag-Asa Hall	3	Rolls	5,800.00	17,400.00
XLR Male/Female Connectors Installation Site: Pag-Asa Hall	30	Pairs	450.00	13,500.00
Professional Wireless Microphone Installation Site: Pag-Asa Hall, HRMO Conference Room	2	Sets	25,000.00	50,000.00
Microphone Stand Installation Site: Pag-Asa Hall	2	Pieces	3,200.00	6,400.00
Loudspeaker Management System Installation Site: Pag-Asa Hall	1	Unit	32,500.00	32,500.00
Equalizer - Dual 31 Band - Frequency Range: 20Hz to 20kHz Installation Site: Pag-Asa Hall	1	Unit	19,500.00	19,500.00
Cabling Connectivity, other accessories on the installation of equipment, configuration testing and commissioning Installation Site: Pag-Asa Hall	1	Lot	219,838.00	219,838.00
Digital Conference Controller - Power Supply - AC220V - Audio Output - RCA, standard connector, XLR - Audio Input – RCA	1	Unit	89,999.00	89,999.00

Installation Site: Admin Conference Room				
Digital Conference Extension Unit - Power supply - AC220V Installation Site: Admin Conference Room	1	Unit	54,999.00	54,999.00
Conference Chairman Unit, Built-in Speaker - Power - DC20V - Frequency Response - 100Hz-10kHz - Gooseneck Length - 400mm Installation Site: Admin Conference Room	1	Unit	13,799.00	13,799.00
Conference Delegate Unit, Built-in Speaker - Power - DC20V - Frequency Response - 100Hz-10kHz - Gooseneck Length - 400mm Installation Site: Admin Conference Room	19	Units	13,799.00	262,181.00
Portable UHF Wireless Microphone - Dual UHF Microphone - 16 Selectable Frequencies - USB Rechargeable Lithium Battery with AA Battery Adapter - LCD Display Installation Site: Admin Conference Room, PETRU Auditorium	2	Sets	8,164.00	16,328.00
Audio/MIDI Interface with MIDAS Preamp Installation Site: Admin Conference Room, PETRU Auditorium	2	Units	12,264.00	24,528.00
Power Sequence Controller	2	Units	8,164.00	16,328.00
18U Equipment Rack Installation Site: Admin Conference Room, PETRU Auditorium	2	Units	29,289.00	58,578.00
Equipment Rack Power Strips and Accessories Installation Site: Admin Conference Room, PETRU Auditorium	2	Units	14,196.00	28,392.00
Conduit, Wires, Speaker Cables, Hangers and Accessories, Cabling Connectivity, other accessories needed in the installation of equipment, configuration testing and commissioning Installation Site: Admin Conference Room	1	Lot	120,679.00	120,679.00

Conduit, Wires, Speaker Cables, Hangers and Accessories, Cabling Connectivity, other accessories needed in the installation of equipment, configuration testing and commissioning Installation Site: PETRU Auditorium	1	Lot	109,137.00	109,137.00
Cabling Connectivity, other accessories needed on the installation of equipment, configuration testing and commissioning Installation Site: HRMO Conference Room	1	Lot	66,100.00	66,100.00
REQUIREMENTS				
<ol> <li>The bidders must be continuously operating in the Philippines for the past five (5) years.</li> <li>The bidders must have no pending case(s) against the government through submission of a notarized Certificate of No Pending Case(s) against the Government, as part of the bid.</li> <li>The bidders must have a professional and technical expert with relevant certifications and training specifically for the installation of audio and video systems.</li> </ol>				
SCOPE OF WORK				
The scope of works includes the supply, delivery, installation and training of personnel on the use of the audio and video equipment systems with the indicated technical specification below. Further, the supplier shall:  1. be responsible in ensuring safe and timely delivery of the equipment to the specified location(s) which includes coordinating logistics, packaging, and transportation;  2. facilitate proper installation of the audio and video equipment to ensure they function correctly and ensuring all components are integrated seamlessly;  3. conduct rigorous testing and commissioning of all equipment to ensure proper functionality and compliance with performance standards; and,  4. conduct training sessions to maximize the effectiveness of the equipment and to educate personnel on how to use and maintain the audio and video systems.				

This training typically covers topics such
as equipment operation,
troubleshooting, maintenance, and
safety procedures.
DELIVERY, INSPECTION AND
ACCEPTANCE
1. The audio and video equipment
systems must be delivered and installed
within sixty (60) calendar days upon
receipt of the Notice to Proceed (NTP);
2. Deliveries and installation should be
made within office hours and on regular
working days on or before the stipulated
date in the contract, unless otherwise
specified for valid reason why the same
cannot be complied with;
3. NCMH shall impose penalty of 1/10 of
1% if the total value of the undelivered
order for each day of delay as liquidated
damages after the specified allowable
number of days to deliver the units.
4. NCMH shall have the right to reject and
return the unit(s) and cancel the
corresponding Contract if units
delivered are defective, incomplete or
noncompliant to the specifications
herein specified.
TERMS OF PAYMENT
The property shall be done within thirty (20)
The payment shall be done within thirty (30)
working days upon submission of complete
documents including Inspection and
Acceptance Report by the
authorized/designated representatives of
NCMH
WARRANTY AND AFTER SALES
1. One (1) year warranty for parts and
service on all deliverables/items.
During the warranty period, the supplier
shall provide technical personnel free of
charge to service the system and all its
components/peripherals whenever
hardware and/or related problem
should occur. Should there be a need to
pull-out a unit for repair, a replacement
unit with at least the same specifications
must be provided by the supplier before
actual pull-out of the malfunctioned unit.

After Sales Service and Support during the warranty period, all reported defects shall be completely/satisfactorily repaired/replaced by the supplier		
	TOTAL AMOUNT	PHP 6,301,508.00

Submitted by:

TRISTIAN JOHN O. PALMANI, RN, MMHOA

(End-User)

Recommending Approval:

ALDEN C. CUYOS, MD, FPPA, IFAPA, MMHoA Chairperson, BAO for Equipment CY2023

Approved by:

NOEL V. REYES, MD, FPPA, MMHoA

Medical Center Chief II