



**NATIONAL CENTER FOR MENTAL HEALTH
PLANNING AND DEVELOPMENT SECTION
BILL OF QUANTITIES**

PLN Bill of Quantities
Rev. 0
15 Oct 2021

PROJECT TITLE: Completion of Pavilion 2 Out-Patient Section Extension
LOCATION: NCMH Compound, 9 de Pebrero, Mauway, Mandaluyong City

ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	MATERIAL COST	LABOR COST	DIRECT COST	MARK-UP IN PERCENT		TOTAL MARK-UP	VAT	TOTAL INDIRECT COST	TOTAL COST
								OCM	PROFIT	%			
1	GENERAL REQUIREMENTS												
	a. Mobilization	1.00	lot										
	b. 4' x 8' Tarpaulin	3.00	pc.										
	c. 1/2" Plywood	3.00	pc.										
	d. Lumber, Assorted	130.00	bd.ft										
	e. Common Wire Nails, Assorted	2.00	kg.										
2	EARTHWORKS												SUB-TOTAL
	a. Excavation (Adobe Soil)	2.00	cu.m										
	b. Gravel	1.00	cu.m										
	c. Soil Poisoning	165.00	sq.m										
3	COVERED WALKWAY AND CANOPY WORKS												SUB-TOTAL
	a. Concrete (Class "A" Ready Mixed)	33.00	cu.m										
	b. Gravel	8.00	cu.m										
	c. 12mm, DSB, Grade 40	45.00	pc.										
	d. 10mm, DSB, Grade 40	255.00	pc.										
	e. #16 G.I. Tie Wire	53.00	kg.										
	f. 1/2" Phenolic Board	6.00	pc.										
	g. Lumber, Assorted	130.00	bd.ft										
	h. Common Wire Nail, Assorted	15.00	kg.										
	i. 2" x 6" x 6mm thk. Tubular	17.00	pc.										
	j. 2" x 4" x 3mm thk. Tubular	15.00	pc.										
	k. 2" x 4" x 2mm thk. Tubular	15.00	pc.										
	l. 2" x 3" x 2mm thk. Tubular	33.00	pc.										
	m. Twin Wall Polycarbonate	170.00	lm										
	n. 200mm x 200mm x 16mm thk. Base Plate, 4-18mm Hole	34.00	pc.										
	o. 16mm A307 Anchor Bolt w/ Standard Nuts & Washer	136.00	pc.										

