

	d. Nylon String	7.00	roll											
	e. Concrete Nail, Assorted	25.00	kg.											
	f. Cement	375.00	bag											
	g. Sand	44.00	cum											
6	CEILING & DRYWALL SYSTEMS WORKS												SUB-TOTAL	
	a. Double Metal Furring, 19mm x 50mm x 0.6mm, 5m	105.00	pc.											
	b. Carrying Channel, 12mm x 38mm x 1mm, 5m	100.00	pc.											
	c. Wall Angle, 25mm x 25mm x 0.5mm, 3m	50.00	pc.											
	d. W-Clip	1,140.00	pc.											
	e. Hanger Rod	105.00	pc.											
	f. Blind Rivets	15.00	box											
	g. Drill Bit, Assorted	20.00	pc.											
	h. 3.5mm Fiber Cement Board	72.00	pc.											
	i. Metal Tracks, 32mmx102mmx0.5mm, 3m	33.00	pc.											
	j. Metal Studs, 32mmx102mmx0.5mm, 3m	110.00	pc.											
	k. 4.5mm Fiber Cement Board	75.00	pc.											
7	ROOFING SYSTEM WORKS												SUB-TOTAL	
	a. 2" x 6" x 3mm Tubular	7.00	pc.											
	b. 2" x 4" x 2mm Tubular	4.00	pc.											
	c. 2" x 2" x 2mm Tubular	32.00	pc.											
	d. 2" x 3" x 1.5mm C-Purlins	50.00	pc.											
	e. 2" x 4" x 1.5mm C-Purlins	11.00	pc.											
	f. 2" x 6" x 1.5mm C-Purlins	16.00	pc.											
	g. 1 1/2" x 1 1/2" x 1/4" Angle Bar	5.00	pc.											
	h. 0.6mm Rib Type Roof, Blue	182.00	lm											
	i. 0.5mm x 36" Flashing, 8'	28.00	pc.											
	j. 10mm Double-Sided Roof Insulation Foam	160.00	lm											
	k. 2 1/2" Tekcrew	900.00	pc.											
	l. 16mm MS Plate	2.00	pc.											
	m. 12mm Plain Bar Gr.40 (Sag Rod)	6.00	pc.											
	n. 16mm x 450mm Anchor Bolt (A307)	48.00	set											
	o. 12mm x 150mm Anchor Bolt (A307)	56.00	set											
	p. Silicone Sealant	18.00	tube											
	q. Welding Rod	100.00	kg.											
	r. Elastomeric Roof Sealant	8.00	ltr.											
	s. Polyulf w/ Hardener	5.00	ltr.											
	t. Epoxy Primer, Gray	10.00	gal.											

